PUBLIC ADVERTISEMENTS.

MYSORE DISTRICT.

Abstract notice dated *February* 1912.

It is hereby notified that sealed tenders will be received by the District Forest Officer, Mysore District, up to 4 P.M., of 6th March 1912 for the purchase of the right to cut and remove timber numbered and marked in the several forests and coups of the Hunsur Range, Mysore District. For particulars, *vide* page 294 of the *Mysore Gazette*, dated 22nd February 1912.

B. HEERA SINGH,
District Forest Officer.

BANGALORE DISTRICT.

MYSORE STATE LIFE INSURANCE.

Dated 19th February 1912.

The attention of the official public is drawn to Notification dated 1st February 1911, published in the *Mysore Gazette* dated 9th, 16th and 23rd February 1911, and to inform that the undersigned will be in the headquarters from the 1st to 20th of every month, as after the latter date he will be out in the district to attend to outdoor Medical and Sanitary duties.

It need not be written to him to ascertain when it would be convenient for any body to be examined for Insurance, as he will be found in the office between 1 and 5 P.M. on those days.

V. MUTHUSAMI DOSS,
District Medical and Sanitary Officer.

BANGALORE CITY MUNICIPALITY.

Notice dated 19th February 1912.

Notice is hereby given that sealed tenders will be received by the President, City Municipality, for dismantling the remaining portion of fort wall, from Albert Victor Road towards north, up to 9th March 1912.

2. Plans and detailed estimate can be seen in the Municipal Engineer's office during office hours.

3. The approximate quantities and items of works to be carried out are given below.

4. The work will be measured as usual by "Sakshigudde." Out of the total quantity thus obtained, the quantity of stones will be deducted and the balance paid as earthwork. The earth to be thrown into the trench lying between the old fort and Hosur road. After lowering the wall to the required level which will be given by the Engineer, the place should be cleared of all mounds, rubbish, etc., and left in a neat way without which full rates will not be passed.

5. Stones will be stacked in measurable heaps of sizes that may be decided by the Engineer, on glacis or other convenient places the Engineer may point out from time to time. Stones of half a cubic foot or less should not be stacked with stones but should be thrown into the trench. Payments for stone work will be made on measurements of heaps after deducting 30 per cent or 40 per cent for crevices according to the way in which they are stacked.

6. Each tenderer must definitely state the rate at which he would carry out each item. The work must be completed by the 10th of June 1912.

7. Tenders must be accompanied by a deposit of Rs. 200 (in cash or currency notes) as earnest money and be superscribed "Tender for dismantling fort wall."

8. Final acceptance of any tender rests with the President, City Municipality, who does not bind himself to accept the lowest or any tender.

9. The name of the successful tenderer whose tender has been accepted will be posted on the Notice Board in the Municipal Engineer's Office in due course.

No enquiries regarding the acceptance or rejection of a tender will receive any attention.

10. The successful tenderer will be required to execute a bond within a week after the acceptance of his tender. In default, the tenderer will forfeit his earnest money and his contract will be considered null and void.

11. The earnest money of rejected tenderers will be returned to them on the above or any subsequent date by the President, City Municipality.

Items of work	*Per*	*Approximate quantity.*
Earthwork, dismantling the fort wall and filling the moat	C. yd.	6,292
Dismantling stone in clay	,,	1,618

N. SUBBA RAO,
For *President.*